KADUR DIVISION.

ADVERTISEMENT.

The 4th June 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 1891, for opening the new right bank Channel to the Keresante Tank Kadur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 to 5.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for opening the new right bank Channel to the Kerasante Tank, Kadur Taluk," in default of which, tenders will be rejected.

5 The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Opening the new right bank Channel to the Keresante Tank, Kadur Taluk.

Items of Work.	Per.	Rate.	Quantity.
Anekat, 200 *feet long.*			
Benching rock	C. Ft.		1,052
Excavating foundation soft rock mixed with earth .. .	C. Yd.		36
Burnt brick in surki mortar	C. Ft.		1,354
Rough stone (hearting) of good quality with mortar	C. Yd.		55
Burnt stone slabs set in mortar	S. ft.		945
Surki mortar plastering	Sq.		18·60
Do pointing	Sq.		10·00
Rough stone work, dry	C. Yd.		240
Teak wood shutter for scouring sluice	C. Ft.		·4
Earthwork watering and tamping	C. Yd.		3,600
Head Sluice, 2 *Vents* 3′×4′.			
Excavating foundation soft rock	C. Yd.		·83
Burnt brick in surki mortar	C. ft.		1,714
Burnt stone slabs set in mortar	S. Ft.		255
Surki mortar plastering	Sq.		13·26
Teak wood shutters	C. ft.		11
Rough stone work, dry	C. Yd.		·84
Channel.			
Excavating soft rock and gravel mixed with stone boulders ..	C. Yd.		5,500
Ordinary soil excavating	C. Yd.		10,890
Relieving weirs, ordinary design	Ft.		80
Madabayi sluices	Each.		8
Cattle bridges	Do		·4
Index stones	Do		69
Grade stones	Do		·73

A. GOVINDACHARLU,
Executive Engineer.

BANGALORE CITY MUNICIPALITY.

NOTICES.

The 24th May 1891.

ELECTION OF MEMBERS FOR THE MYSORE REPRESENTATIVE ASSEMBLY, 1891.

WITH reference to Rule 3 of Government Notification No. 76 of the 14th May 1891, published in the *Mysore Gazette* of the 16th idem, it is hereby notified for the information of the public that a Meeting of persons qualified to become Members of the Mysore Representative Assembly of 1891, will be convened at 8 A. M., on Saturday, the 11th July next, at the City Municipal Office in the Fort.

List of qualified persons will be published shortly.